



Goddard Park Community Primary School

Specification For Year 4 Extension

DESCRIPTION	COST	TOTAL COST
Supply all facilities, plant and storage to carry out the project in line with all current Health and Safety/CDM regulations		
Identify and isolate any existing services effected by the the work.		
Carry out necessary groundworks to existing slabbed area		
Remove current canopy		
Supply and fit necessary steelwork to create new opening in current external wall		
New lintels and reinforced jambs to form new opening and support existing lintel		
Create new corridor from stud work leading to new external entrance as per Architects drawing.		
Supply access door and steps for access to existing services.		
Install new electrical sockets as per drawing number 2		
install new UPVC doors to external wall of building		
Relocate existing window as per Architects drawing		

DESCRIPTION	COST	TOTAL COST
Relocate current manhole covers or supply sealed ECO cover for inside of room		
Allow for any re-fitting of previously set aside fixtures and fittings		
Contingency for unknown/potential additional costs		
Leave the site clean and tidy (to include any costs relating to skips etc)		